



GROWTH MANAGEMENT DEPARTMENT STAFF REPORT
MID-ANASTASIA DESIGN OVERLAY DISTRICT

March 10, 2022 Public Meeting
MADRB 2021-06 Anastasia Baptist Church

To: Mid-Anastasia Design Review Board

From: Saleena Randolph, Planner

Applicant: Brian Couch
KBJ- L&B Architects
50 N. Laura Street, Suite 4200
Jacksonville, FL 32202

Owner: Anastasia Baptist Church

Location: 1650 A1A South

Zoning / FLUM: Residential, Single Family (RS-3) / Residential-C (Res-C)

Applicable Standards: Land Development Code (LDC), Part 3.08.00



Summary of Request: The applicant requests design approval for demolition of the existing Educational/Administration Buildings and detached office building, and approval for construction of two new buildings to include an Education/Administration Building and a Gymnasium.

STAFF COMMENTS

The applicant is requesting the Board's review and approval for the following: demolition of the existing Educational/Administration Buildings, demolition of the existing detached office building, construction/design review of a new 47,754 square foot Educational/Administration Building, construction/design review of a new 13,130 square foot Gymnasium, and revised parking and landscaping where applicable. The Non-Zoning Variance is discussed separately, and this report covers only the design review of the proposed site.



Based on application materials provided by the applicant, the location of the proposed Education/Administration building has been designed to allow for construction of the new building while the existing building will remain in use. The new Education/Administration building will be set back further away from A-1-A as compared to the existing Education/Administration building. The proposed Education/Administration building fronting SR A1A South will not encroach within the 30-foot required setback for a building over 20 feet in height as required in LDC Section 3.08.05.A.

Based on the application materials, the new Gymnasium will be built behind the Family Life Building and appears to be proposed near the existing detached office building that is planned for removal. The new Gymnasium will be set back further away from Old Beach Road as compared to the existing office building. This building fronting Old Beach Road will not encroach within the 20-foot required setback for a building over 20 feet in height as required in LDC Section 3.08.05.B.



Additional buffering and screening requirements prescribed within in Section 3.08.06 are existing and are not being revised. Staff notes that a Landscaping Plan was provided as a part of this request. Section 3.08.06.A.1 allows a twenty (20) foot buffer from the right-of-way of State Road A1A South except on Scenic Highway A1A as described in 6.06.02.F.2.b. This site is on Scenic Highway A1A; therefore, according to Section 6.06.02.F.2.b, a minimum 30-foot buffer is required along A1A South. The minimum 30-foot buffer is currently provided and will not be revised as part of this proposed development. According to Section 3.08.06.A, a minimum 15-foot buffer is required along Old Beach Road and this buffer is not being provided. The current buffer is 8 feet and is not being revised or disturbed, and this area of the site and buffer along Old Beach Road does not appear as being proposed for revision.

With respect to the design elements and materials proposed for the buildings, the applicant states that the proposed exterior wall coverings/colors and proposed roofing material will match the existing buildings, as previously approved. Any proposed changes to this application, as submitted, will require additional review by the Mid-Anastasia Design Review Board.



Artist Renderings:



Section 3.08.01 Purpose and Intent

The purpose and intent of this Special District is to achieve specific goals and objectives of the St. Johns County Comprehensive Plan and establish additional requirements which regulate development in a manner that protects natural resources and further supports the provisions of Article IV of this Code, and maintains and enhances the diverse and unique character of the Mid- Anastasia Overlay District.

The objective of these requirements is to protect surrounding residential Uses; cluster complementary Uses; protect scenic views; enhance physical appearance through design and signage controls; protect community character and encourage pedestrian activity. These objectives shall be accomplished through the establishment and implementation of special guidelines, standards and criteria which shall apply to the location, character, compatibility and appearance of proposed cultural, institutional, commercial and multi-family land Uses, and to certain changes or renovations to such existing land Uses. The implementation of this Part shall be assisted by a Design Review Board, which shall be established in accordance with the administrative procedures of this Part. The review of activities which are subject to these additional requirements shall be performed with the goal of determining whether a proposed activity meets the goals, objectives and policies set forth in the Comprehensive Plan and the guidelines, standards and criteria of this Part.

Relevant Code Sections – Design Review; LDC Part 3.08.00

- 3.08.04 Development Standards
- 3.08.05 Minimum Yard Requirements
- 3.08.06 Additional Buffer Requirements
- 3.08.08 Design Review Guidelines
- 3.08.09 Design Elements and Material

SUGGESTED ACTION TO APPROVE

The Design Review Board may consider a motion to approve **MADRB 2021-06 Anastasia Baptist Church**, as described within the application and supporting documents provided:

1. The request complies with the required design standards prescribed within Part 3.08.00 of the St. Johns County Land Development Code.

SUGGESTED ACTION TO DENY

The Design Review Board may consider a motion to deny **MADRB 2021-06 Anastasia Baptist Church**, as described within the application and supporting documents provided:

1. The request does not comply with the design standards prescribed within Part 3.08.00 of the St. Johns County Land Development Code.

ATTACHMENTS:

1. Application and Supporting Documents
2. LDC, Part 3.08.00 Mid-Anastasia Overlay District
3. Draft Final Orders

ATTACHMENT 1
APPLICATION AND SUPPORTING
DOCUMENTS



Application for Overlay District Review
 Growth Management Department
 Planning and Zoning Section
 4040 Lewis Speedway, St. Augustine, FL 32084
 Phone: 904.209.0675; Fax: 904.209-0576

Date Overlay District Property ID No (Strap)

Applicant Phone Number

Address Fax Number

City State Zip Code E-mail

Project Name

Project Address & Location

Type of Review Commercial Use Multi-family Use Other:
 Check all that apply

The Project Involves New Building Changes to an existing Building Exterior Repainting Signage (Individual)
 Check all that apply
 Unified Sign Plan Fences / Walls Parking / Lighting Landscaping / Buffers
 Other:

Describe Project and work proposed to be done (Provide additional information by attachment as needed)

Demolition of Existing Educational and Administration Buildings
 New Educational and Administration Building
 New Gymnasium
 New Parking

I HEREBY CERTIFY THAT ALL INFORMATION IS CORRECT:
 Signature of owner or person authorized to represent this application:

Brian Couch
 Signed By


Printed or typed name(s)

Contact Information of person to receive all correspondence if different than applicant:

Phone Number Fax Number E-mail
 Postal Address Name
 City State Zip Code

Please notify the Planning and Zoning Section at 904.209.0675 if you need any special assistance or accommodations to attend the meeting or if you have any questions concerning this application.

Please list any applications currently under review or recently approved which may assist in the review of this application including the name of the PUD/PRD:



SITE DATA TABLE		
TOTAL SITE	9.78 AC	425,973 SF
EXISTING BUILDING		42,588 SF
EXISTING IMPERVIOUS AREA		178,982 SF
PROPOSED BUILDING		29,963 SF
PROPOSED IMPERVIOUS AREA		45,603 SF
TOTAL IMPERVIOUS		224,585 SF
TOTAL PERVIOUS		201,388 SF
TOTAL IMPERVIOUS %		53%
TOTAL PERVIOUS %		47%
% BUILDING COVERAGE		17%
TOTAL FLOOR AREA		193,261 SF
FLOOR AREA RATIO (FAR)		45.4%
PARCEL NUMBER(S)		(EX. 206440 0020)
911 ADDRESS		1650 A1A SOUTH
FEMA PANEL NUMBER		12109C0381J, 12109C0382J
FLOOD ZONE		ZONE X
SETBACKS (FRONT/SIDES/BACK)		30/20/20'

PARKING CALCULATIONS		
TOTAL PARKING EXISTING	=	331 SPACES
TOTAL ADA EXISTING	=	16 SPACES
TOTAL EXISTING REMOVED	=	38 SPACES
TOTAL ADA EXISTING REMOVED	=	4 SPACES

SHEET NO. 1 OF XX
 CLIENT: ST. JOHNS COUNTY
 ANASTASIA BAPTIST CHURCH
 MASTER SITE PLAN

REGISTERED ENGINEER
 C. P. E., P. E.
 C. P. E. #17811
 C. P. E. #17811

MATTHEWS DESIGN GROUP
 P.O. BOX 3126, 7 WALDO STREET
 ST. AUGUSTINE, FL 32084
 PHONE: 904.826.1334 • FAX: 904.826.4547
 INFO@MDGINC.COM

NO.	DATE	DESCRIPTION

JOB NO. 21088
 DATE: XX-XX-XX
 DRAWN BY: RAM
 CHECKED BY: XXX
 CLIP NO.

C:\PROJECTS\2024\08\ANASTASIA BAPTIST CHURCH\CONSTRUCTION DOCUMENTS\JOB MASTER SITE PLAN.DWG, 11/14/24, 11:44 AM, E:\11-14-24\MATTHEWS DESIGN GROUP, INC.

PLANT SCHEDULE

TREES	CODE	BOTANICAL NAME	COMMON NAME	CONTAINER	SIZE	QTY	DETAIL	REMARKS
	IE	Ilex x attenuata 'Eagleston'	Eagleston Holly	---	6" Cal. / 14' Ht.	2		
	JS	Juniperus silicicola	Southern Red Cedar	---	6" Cal. / 14' Ht.	11		
	LN	Lagerstroemia indica x fauriei 'Natchez'	Natchez Crape Myrtle	---	6" Cal. / 14' Ht.	3		Multi-trunk
	QC	Quercus virginiana	Live Oak	---	6" Cal. / 14' Ht.	8		

Percentage	Tree	Caliper"	Count	Total Inches
8.33%	HOLLY	6	2	12
45.83%	CEDAR	6	11	66
12.50%	CRAPE	6	3	18
33.33%	OAK	6	8	48
			24	144

TREE REQUIREMENT CALCULATIONS



MINIMUM TREE REQUIREMENT = 80 INCHES/ ACRE
 SITE AREA = 1.40 ACRES
 MINIMUM TREES INCHES = 112 INCHES
 REQUIRED = 112 INCHES
 PRESERVED TREES INCHES + PLANTED TREE INCHES = TOTAL TREE INCHES
 15 + 144 = 159 INCHES

SIC TREE MITIGATION REQUIREMENT

PLANTED TREE INCHES MUST BE ≥ REMOVED PROTECTED TREE INCHES
 REMOVED PROTECTED TREE INCHES = 666 INCHES
 PLANTED TREE INCHES = 144 INCHES
 144 < 666

NOTES:

- 70% OF NEWLY PLANTED TREES MUST BE CANOPY TREES.
- NO MORE THAN 50% OF NEWLY PLANTED TREES CAN BE OF THE SAME SPECIES.
- VEGETATION THAT EXCEEDS TWENTY-FIVE (25) FEET IN HEIGHT AT MATURITY SHOULD NOT BE PLANTED CLOSER THAN FIFTEEN (15) FEET OF THE VERTICAL PLANE OF AN EXISTING POWER LINE, EXCLUDING SERVICE WIRES.
- BALLED AND BURLAPPED STRAPPING WIRE, AND ANY SYNTHETIC MATERIAL SHALL BE REMOVED PRIOR TO FINAL INSPECTION. WIRE BASKETS SHOULD BE CUT AWAY FROM TOP ONE-THIRD OF ROOT BALL.
- NON-CANOPY TREES SHALL NOT BE PLANTED CLOSER THAN 10 FEET FROM OTHER TREES AND CANOPY TREES NO CLOSER THAN 20-30 FEET, DEPENDING ON SPECIES.
- PLANT MATERIAL SHALL CONFORM TO THE STANDARDS FOR GRADE #1 OR BETTER AS GIVEN IN THE LATEST "GRADES AND STANDARDS FOR NURSERY PLANTS, PART I AND II," FLORIDA DEPARTMENT OF AGRICULTURE AND CONSUMER SERVICES OR TO THE STANDARDS AS GIVEN IN THE LATEST "AMERICAN STANDARD FOR NURSERY STOCK", AMERICAN NATIONAL.
- PINE BARK OR PINE STRAW MULCH SHALL BE PROVIDED A MINIMUM OF TWO TO THREE INCHES IN DEPTH AROUND ALL NEWLY PLANTED LANDSCAPE.
- A MULCH RING FOR ALL NEWLY PLANTED TREES SHALL BE PROVIDED AT LEAST FIVE (5) FEET IN DIAMETER AND NOT CLOSER THAN SIX (6) INCHES FROM THE TREE TRUNK.
- IRRIGATION WILL BE PROVIDED WITH AN AUTOMATIC IRRIGATION SYSTEM.
- TREES SHALL HAVE A MINIMUM HEIGHT OF EIGHT (8) TO TEN (10) FEET AND TWO (2) INCHES OF CALIPER.
- SHRUB LINES ARE TO BE PLANTED AT THE REQUIRED MINIMUM HEIGHT, NOT BY CONTAINER SIZE.
- SOIL IN TREE ISLAND SHALL HAVE AT LEAST 12" OF SUITABLE SOIL FOR TREE PLANTINGS, AND BE VOID OF ANY CONSTRUCTION DEBRIS OR UNSUITABLE MATERIALS.
- TREES SHALL NOT BE PLANTED CLOSER THAN 7.5" FROM THE CENTERLINE OF UNDERGROUND UTILITIES.



© PRODUCED BY 10/20/2018 - ANASTASIA BAPTIST CHURCH/ENDOWMENT/CONSTRUCTION DOCUMENT/10/18 - LANDSCAPE PLAN/REV. L1 - 2/25/2023 11:12 AM - EXCLUSIVE: MATTHEWS DESIGN GROUP, INC.

LANDSCAPE PLAN

ANASTASIA BAPTIST CHURCH

ST. JOHNS COUNTY

PREPARED FOR CLIENT

MATTHEWS DESIGN GROUP

P.O. BOX 3126, 7 WALDO STREET
 ST. AUGUSTINE, FL 32084
 PHONE: 904.826.1334 • FAX: 904.826.4547
 INFO@MDGINC.COM

NO.	DATE	REVISIONS DESCRIPTION


DESIGN BY:	E.J.L.
DRAWN BY:	E.J.L.
CHECK BY:	E.J.L.
DATE:	NOV. 2021
JOB NO.:	21088

2


OF XX

REGISTERED LANDSCAPE ARCHITECT
 STATE OF FLORIDA
 CERT. NO. CA29535 FL. #668977


This plan has been digitally signed and sealed. CHECKS, BATTENMARKS, ETC. shall also appear on the plan. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.




SHRUB AND GROUND COVER PLANTING DETAIL




SHRUB/GROUNDCOVER SPACING PLAN



STAKING DETAIL




NATIVE SHRUB PLANTING




ALL PROTECTED TREES, PRESERVED UNDERSTORY VEGETATION, AND TREES RETAINED FOR TREE CREDIT SHALL BE PROTECTED FROM INJURY DURING ANY LAND CLEARING AND CONSTRUCTION PROCESS IN THE FOLLOWING MANNER.

1. THE MINIMUM UNDISTURBED AREA SHALL BE DESCRIBED BY A RADIUS OF ONE FOOT FOR EACH INCH OF THE TREE'S DIAMETER AT BREAST HEIGHT. DURING DEVELOPMENT ACTIVITY, ENCROACHMENT INTO THE UNDISTURBED AREA FOR PROPOSED ACTIVITY DESCRIBED IN CC LDC 6-2(S)(E), MAY BE PERMITTED UP TO 25% OF THE RADIUS OR UP TO 50% OF THE RADIUS ON ONE SIDE BUT NOT CLOSER THAN 6 FEET TO THE TRUNK OF THE TREE IN ALL EVENTS.
2. A TEMPORARY BARRIER SHALL BE CONSTRUCTED TO PREVENT DISTURBANCE OF THE SOIL EQUAL TO MINIMUM UNDISTURBED AREA. THE BARRIERS SHALL BE IN PLACE PRIOR TO LAND CLEARING AND REMAIN IN PLACE THROUGHOUT CONSTRUCTION.
3. THE DEVELOPER SHALL NOT CAUSE OR ALLOW THE CLEANING OF EQUIPMENT, STORAGE OR DISPOSAL OF MATERIALS OR WASTE MATERIALS SUCH AS PAINT, SOLVENTS, ASPHALT, CONCRETE, MORTAR, OR ANY OTHER MATERIAL THAT MAY ENDANGER THE HEALTH OF TREES OR VEGETATION WITHIN THE MINIMUM UNDISTURBED AREAS OF PROTECTED TREES.
4. THE MINIMUM UNDISTURBED AREA SHALL BE MAINTAINED AT ITS ORIGINAL GRADE WITH NO TRENCHING OR CUTTING OF ANY ROOTS, AND THERE SHALL BE NO STORAGE OF FILL OR COMPACTION OF SOIL. IN NO EVENT SHALL MOTORIZED VEHICLES OR EQUIPMENT BE ALLOWED TO PARK ON OR TRAVERSE THAT AREA WITHIN THE MINIMUM UNDISTURBED AREA OF THE PROTECTED TREES, NOR SHALL ANY DIRT OR OTHER MATERIALS BE STORED WITHIN THE BARRIERS.
5. NO ATTACHMENT, WIRES (OTHER THAN PROTECTIVE GUY WIRES), SIGNS OR PERMITS SHALL BE FASTENED TO A TREE.
6. ALL CLEARING AND GRUBBING WITHIN PROTECTED TREE AREA WILL BE DONE WITH HAND TOOLS ONLY.
7. ALL ROOT SYSTEMS OUTSIDE THE PROTECTIVE RADIUS WHICH OCCUR IN AREAS OF PROPOSED IMPROVEMENTS SHALL BE PRUNED BY A QUALIFIED TREE SURGEON PRIOR TO EXCAVATION.


TREE PROTECTION FENCING / MIN. UNDISTURBED AREAS



PALM PLANTING FOR UP TO 24' CLEAR TRUNK



WOOD BATTEN DETAIL



WOOD STAKING DETAIL

1 PALM PLANTING

1/4" = 1'-0"

P-CO-15

PLANTING NOTES

1. The LANDSCAPE CONTRACTOR is responsible for verifying project site conditions and all quantities indicated on these plans before commencing any work. LANDSCAPE CONTRACTOR shall notify the LANDSCAPE ARCHITECT if soil conditions are poorly drained to determine if substitution of materials is necessary.
2. All plant material shall be Florida Grade No. 1 or better nursery grown in accordance to Florida Grades and Standards
3. All plant material shall be container grown or B&B. B&B materials shall be "hardened off" root pruned during field production and shall be dug at least several weeks before
4. Plants shall be sound, healthy and vigorous, well branched and densely foliated when in leaf. They shall be free of disease, insects, eggs or larvae and shall have healthy, well developed root systems. They shall be free from physical damage or adverse conditions that would prevent thriving growth.
5. Substitution of plant materials will not be permitted unless authorized in writing by the LANDSCAPE ARCHITECT. If proof is submitted that any plant specified is not obtainable, a proposal will be considered for use of the nearest equivalent size or variety with corresponding adjustment of contract price.
6. LANDSCAPE CONTRACTOR shall bear final responsibility for proper surface drainage of planted areas. Any discrepancy in the drawings, obstruction on the site, or prior to work done by any other party, which the CONTRACTOR feels precludes establishing proper drainage shall be brought to the attention of the LANDSCAPE ARCHITECT for correction or relief of said responsibility.
7. Planting beds shall be cut or edged to form a uniform clean line between beds and lawn areas.
8. After all plant material in a plant bed area has been installed and approved, the areas between plants shall be raked to an even grade to conform to pre-mulching finish grades. All planting beds and plant saucers shall then be uniformly covered with a minimum three (3) inches of #2 grade or better of PINE BARK MINI NUGGETS.
9. Before fertilization a soil and/or foliar nutrient analysis shall be performed to determine whether phosphorus fertilizer with 30% slow release nitrogen will be required. All planting bed areas shall be fertilized approximately 4-6 weeks after installation.
10. Plant material soil shall be "native" soil that was removed from the planting hole. If soil is badly contaminated, good quality soil shall be used as replacement after contaminated soil has been completely removed from planting area.
11. After sodding is completed, the entire side areas shall be watered by hand or irrigation system each day for two weeks. After approximately one month of installation, sodded areas shall then be top dressed with a 15-0-15 commercial slow-release fertilizer at a rate of 6.67 pounds per 1,000 square feet of area in an evenly broad-case pattern.
12. The LANDSCAPE CONTRACTOR is responsible for all fine grading preparation for planting. Apply pre-emergent to all beds prior to planting.
13. Rough grades will be established by the owners general contractor at approximately 3 inches below curbs, sidewalks, hardscape amenities, mowing strips and abutments. All materials shall be a minimum 30" from buildings or walks.
14. Sod areas shall be SPECIFIED Grass. Grass for sodding shall be freshly cut in squares one foot wide by two feet long. Sod shall be healthy, free of insects and weeds, in naturally flourishing conditions. Dry, brown and unrefresh sod will be rejected.
15. Sod shall be laid end to end and side to side in a staggered line to form a uniform layer. All uneven edges shall be squarely trimmed to allow close and firm fitting of each piece.
16. The LANDSCAPE CONTRACTOR is responsible for fully maintaining all plant material on site during and before planting, until the work is accepted by the LANDSCAPE ARCHITECT and/or owner.
17. All plants shall be guaranteed by the LANDSCAPE CONTRACTOR to be healthy plants and in flourishing condition of active growth for ninety (90) days from final inspection and acceptance. All trees shall be guaranteed an additional one year from final inspection and acceptance.
18. The LANDSCAPE ARCHITECT, owner or owners representative shall have the right to reject any and all work which in his opinion does not meet with the requirements of the specifications at any stage of the project operation.
19. There will be special care to all existing trees to be retained on site to avoid construction damage.

© PRODUCED BY 10/20/2008 - ANASTASIA BAPTIST CHURCH/ENDOWMENT/CONSTRUCTION DOCUMENT/10/10/08 - LANDSCAPE PLANNING, L.L.C. 10/20/2008 11:15 AM. E:\Landscape\MATTHEWS DESIGN GROUP, INC.

LANDSCAPE SPECIFICATIONS
ANASTASIA BAPTIST CHURCH
ST. JOHNS COUNTY
PREPARED FOR CLIENT

MATTHEWS DESIGN GROUP
P.O. BOX 3126, 7 WALDO STREET
ST. AUGUSTINE, FL 32084
PHONE: 904.826.1334 • FAX: 904.826.4547
INFO@MDGINC.COM

DESIGN BY:	E.J.L.	DATE:	NOV. 2021
DRAWN BY: <td>E.J.L. <td>NO.</td> <td>21088</td> </td>	E.J.L. <td>NO.</td> <td>21088</td>	NO.	21088
CHECK BY: <td>E.J.L. <td>NO.</td> <td></td> </td>	E.J.L. <td>NO.</td> <td></td>	NO.	
DATE: <td>NOV. 2021 <td>NO.</td> <td></td> </td>	NOV. 2021 <td>NO.</td> <td></td>	NO.	
JOB NO.: <td>21088 <td>NO.</td> <td></td> </td>	21088 <td>NO.</td> <td></td>	NO.	

REGISTERED LANDSCAPE ARCHITECT
E.J.L. MATTHEWS
FL 00000000
CA#27535 FL #669877

EXISTING TREES TO REMOVE REMAIN


TREE NUMBER	TREE COMMON NAME	D.B.H.	TO REMOVE	TO REMAIN
31	LIVE OAK	40"17"	57	
86	LIVE OAK	22"24"	46	
200	LIVE OAK	31		31
201	BOTTLE BRUSH	2"3"3"2"		10
202	BOTTLE BRUSH	2"3"3"2"		7
203	BOTTLE BRUSH	3"2"2"2"		7
204	BOTTLE BRUSH	2"1"1"1"		4
205	CEDAR	12	12	
206	CEDAR	26	26	
207	LIVE OAK	29	29	
208	LIVE OAK	21	21	
209	LIVE OAK	19	19	
210	LIVE OAK	18	18	
211	LIVE OAK	18	18	
212	LIVE OAK	14	14	
213	LIVE OAK	14	14	
214	LIVE OAK	24	24	
215	SABAL PALM	120. A.	3	
216	LIVE OAK	22	22	
217	LIVE OAK	33	33	
218	SABAL PALM	120. A.	3	
219	LIVE OAK	15		15
220	QUEEN PALM	28	6	
221	QUEEN PALM	20	6	
222	LIVE OAK	15	15	
223	LIVE OAK	15	15	
224	LIVE OAK	8	8	
225	LIVE OAK	15	15	
226	LIVE OAK	15	15	
227	LIVE OAK	11	11	
228	CEDAR	12	12	
229	LIVE OAK	18"26"	44	
230	LIVE OAK	27	27	
231	LIVE OAK	15	15	
232	LIVE OAK	24	24	
233	CEDAR	14	14	
234	ELM	5	5	
235	LIVE OAK	13	13	
236	LIVE OAK	21	21	
237	LIVE OAK	22	22	
238	LIVE OAK	19	19	

TOTALS 666 74

EXISTING TREES TABLE

TREE #	TREE SIZE AND SPECIES	TREE #	TREE SIZE AND SPECIES	TREE #	TREE SIZE AND SPECIES
1	13" OAK	62	41" OAK	119	10" PALM
2	24" OAK	63	8" PALM	120	12" PALM
3	22" OAK	64	15" CEDAR	121	11" PALM
4	24" OAK	65	23" CEDAR*	122	10" PALM
5	18" OAK	66	17" CEDAR	123	12" PALM
6	14" PALM	67	29" OAK	124	12" PALM
7	27" OAK	68	5" X 6" X 6" X 7" X 8" ORANGE TREE	125	8" CRATE MYRTLE CLUSTER
8	24" OAK	69	32" OAK	126	6" CRATE MYRTLE CLUSTER
9	30" OAK	70	8" X 14" OAK	127	8" OAK
10	30" OAK	71	18" OAK	128	8" OAK
11	8" OAK	72	34" OAK	129	36" CRATE MYRTLE CLUSTER
12	11" OAK	73	17" OAK	130	15" OAK
13	7" OAK	74	9" OAK	131	14" X 8" OAK
14	13" OAK	75	17" CEDAR	132	8" X 8" OAK
15	14" OAK	76	53" OAK	133	23" OAK
16	13" OAK	77	24" CEDAR	134	14" X 12" X 8" OAK
17	13" OAK	78	18" ELM	135	12" OAK
18	7" HOLLY	79	24" CEDAR	136	14" OAK
19	20" OAK	80	23" CEDAR	137	24" OAK
20	17" OAK	81	24" PALM	138	24" OAK
21	18" OAK	82	24" PALM	139	30" OAK
22	17" OAK	83	14" OAK	143	16" OAK*
23	18" OAK	84	24" OAK	144	8" ELM*
26	9" X 9" X 9" X 12" X 14" OAK CLUSTER	85	20" X 27" X 15" X 18" OAK	145	7" HOLLY*
27	11" X 18" X 24" X 28" OAK CLUSTER	86	22" X 24" OAK	146	6" CEDAR*
28	16" ELM	88	14" CRATE MYRTLE	147	18" OAK*
29	24" ELM	89	16" PALM*	148	32" OAK*
31	40" X 17" OAK	90	11" OAK	149	36" OAK
32	9" X 9" X 8" FLAME TREE	91	11" OAK	150	21" OAK
33	18" CEDAR TREE	92	13" OAK	151	19" OAK
34	20" CEDAR	93	10" OAK	152	12" OAK
35	14" CEDAR	94	15" OAK	153	11" FUR
36	14" CEDAR	95	8" OAK	154	6" MAG
37	17" CEDAR	96	14" OAK	155	7" MAG
38	15" OAK	97	7" OAK	156	12" PALM
39	17" OAK	98	6" MAG	157	14" PALM
40	44" OAK	100	10" PALM	158	15" OAK
41	36" OAK	101	10" PALM	159	16" PALM
42	36" OAK	102	12" OAK	160	17" PALM
43	16" OAK	103	13" X 13" OAK		
44	16" OAK	104	13" X 9" OAK		
45	24" BY 20" OAK	105	20" OAK*		
46	8" PALM	106	16" OAK		
47	8" PALM	107	16" OAK		
48	23" OAK	108	14" OAK		
49	18" OAK	109	32" OAK		
50	34" OAK	110	60" OAK		
51	26" OAK	111	15" PALM		
52	28" OAK	112	16" PALM		
53	27" OAK	113	16" PEAR		
54	15" CEDAR	114	8" MAG		
55	16" CEDAR	115	11" PALM		
56	15" CEDAR	116	11" PALM		
57	24" OAK	117	11" PALM		
58	25" OAK	118	11" PALM		
59	13" CEDAR				
60	12" CEDAR				
61	15" OAK				

LEGEND
 200 ○ TREE TO REMAIN
 221 ✕ TREE TO BE REMOVED



MATTHEWS DESIGN GROUP
 P.O. BOX 3126, 7 WALDO STREET
 ST. AUGUSTINE, FL 32084
 PHONE: 904.826.1334 • FAX: 904.826.4547
 INFO@MDGINC.COM

ANASTASIA BAPTIST CHURCH
 ST. JOHNS COUNTY
 PREPARED FOR CLIENT

TREE INVENTORY

GRAPHIC SCALE
 0 30 45 60
 1"=30'

SHEET NO. 4 OF XX

© PRODUCED BY 10/20/2018 - ANASTASIA BAPTIST CHURCH/ENGINEERING/CONSTRUCTION DOCUMENT/10/18 - LANDSCAPE PLAN/REV. L1 (3) 10/20/2018 11:15 AM E:\Landscape\MATTHEWS DESIGN GROUP, INC.

MID-ANASTASIA DESIGN REVIEW BOARD



ANASTASIA BAPTIST CHURCH
St. Augustine, Florida



TABLE OF CONTENTS:

- **PROJECT LOCATION**
- **PROJECT SCOPE**
 - SITE PLAN
 - LANDSCAPE
 - FLOOR PLANS
 - ELEVATIONS
- **ADDITIONAL INFORMATION**
 - MAXIMUM BUILDING LENGTH
 - ROOF DESIGN
- **RENDERINGS**



ANASTASIA BAPTIST CHURCH

St. Augustine, Florida





PROJECT LOCATION

ANASTASIA BAPTIST CHURCH
St. Augustine, Florida



LOCATION



ANASTASIA BAPTIST CHURCH
St. Augustine, Florida



LOCATION



SITE LOCATION

**1650 A1A S, ST. AUGUSTINE
PROPERTY BOUNDARY**



ANASTASIA BAPTIST CHURCH

St. Augustine, Florida



PROJECT SCOPE



ANASTASIA BAPTIST CHURCH
St. Augustine, Florida



PROJECT SCOPE:

- **CONSTRUCT NEW 3 LEVEL EDUCATION & BUSINESS BUILDING**
 - 47,754 sf Building
 - 6,610 sf Total Business
 - 41,144 sf Total Education
 - 3,100 sf additional Roof Deck Patio
- **CONSTRUCT NEW 1 LEVEL GYMNASIUM WITH STORAGE MEZZANINE**
 - 13,130 sf Building
 - 12,230 sf Gymnasium
 - 900 sf Mezzanine
- **DEMO THE EXISTING 1 LEVEL EDUCATION BUILDINGS & 1 LEVEL BUILDING**
 - 1 Level Education Buildings located off AIA (after construction is complete)
 - 1 Level Office Building located off Old Beach Road



ANASTASIA BAPTIST CHURCH

St. Augustine, Florida



PROJECT SCOPE



ANASTASIA BAPTIST CHURCH
St. Augustine, Florida



PROJECT SCOPE




ANASTASIA BAPTIST CHURCH

St. Augustine, Florida



PROJECT SCOPE



NEW PROJECT SITE PLAN

SITE DATA TABLE		
TOTAL SITE	9.78 AC	425,973 SF
EXISTING BUILDING		42,588 SF
EXISTING IMPERVIOUS AREA		178,982 SF
PROPOSED BUILDING		29,983 SF
PROPOSED IMPERVIOUS AREA		45,603 SF
TOTAL IMPERVIOUS		224,584 SF
TOTAL PERVIOUS		201,388 SF
TOTAL IMPERVIOUS %		53%
TOTAL PERVIOUS %		47%
% BUILDING COVERAGE		17%
TOTAL FLOOR AREA		193,261 SF
FLOOR AREA RATIO (FAR)		45.4%
PARCEL NUMBER(S)		(EX. 208440 0020)
911 ADDRESS		1650 A1A SOUTH
FEMA PANEL NUMBER		12109C0381J, 12109C0382J
FLOOD ZONE		ZONE X
SETBACKS (FRONT/SIDES/BACK)		30'/20'/20'

PARKING CALCULATIONS		
TOTAL PARKING EXISTING	=	331 SPACES
TOTAL ADA EXISTING	=	16 SPACES
TOTAL EXISTING REMOVED	=	38 SPACES
TOTAL ADA EXISTING REMOVED	=	4 SPACES



ANASTASIA BAPTIST CHURCH

St. Augustine, Florida



PLANT SCHEDULE

TREES	CODE	BOTANICAL NAME	COMMON NAME	CONTAINER	SIZE	QTY	DETAIL	REMARKS
	IE	Ilex x attenuata 'Eagleston'	Eagleston Holly	---	6" Cal. / 14' Ht.	2		
	JS	Juniperus silicicola	Southern Red Cedar	---	6" Cal. / 14' Ht.	11		
	LN	Lagerstroemia indica x faunei 'Natchez'	Natchez Crape Myrtle	---	6" Cal. / 14' Ht.	3		Multi-trunk
	OC	Quercus virginiana	Live Oak	---	6" Cal. / 14' Ht.	8		

Percentage	Tree	Caliper"	Count	Total inches
8.33%	HOLLY	6	2	12
45.83%	CEDAR	6	11	66
12.50%	CRAPE	6	3	18
33.33%	OAK	6	8	48
			24	144

TREE REQUIREMENT CALCULATIONS


MINIMUM TREE REQUIREMENT =	80 INCHES/ ACRE	
SITE AREA =	1.40 ACRES	
MINIMUM TREES INCHES REQUIRED =	1.40 ACRES x	112 INCHES
PRESERVED TREES INCHES + PLANTED TREE INCHES = TOTAL TREE INCHES		150 INCHES
	144	112

SIC TREE MITIGATION REQUIREMENT

PLANTED TREE INCHES MUST BE ≥ REMOVED PROTECTED TREE INCHES	
REMOVED PROTECTED TREE INCHES =	666 INCHES
PLANTED TREE INCHES	144 INCHES
144	≥ 666

NOTES:

- 70% OF NEWLY PLANTED TREES MUST BE CANOPY TREES.
- NO MORE THAN 50% OF NEWLY PLANTED TREES CAN BE OF THE SAME SPECIES.
- VEGETATION THAT EXCEEDS TWENTY-FIVE (25) FEET IN HEIGHT AT MATURITY SHOULD NOT BE PLANTED CLOSER THAN FIFTEEN (15) FEET OF THE VERTICAL PLANE OF AN EXISTING POWER LINE, EXCLUDING SERVICE WIRES.
- BALLED AND BURLAPPED STRAPPING WIRE, AND ANY SYNTHETIC MATERIAL SHALL BE REMOVED PRIOR TO FINAL INSPECTION. WIRE BASKETS SHOULD BE CUT AWAY FROM TOP ONE-THIRD OF ROOT BALL.
- NON-CANOPY TREES SHALL NOT BE PLANTED CLOSER THAN 10 FEET FROM OTHER TREES AND CANOPY TREES NO CLOSER THAN 20-30 FEET, DEPENDING ON SPECIES.
- PLANT MATERIAL SHALL CONFORM TO THE STANDARDS FOR GRADE #1 OR BETTER AS GIVEN IN THE LATEST "GRADES AND STANDARDS FOR NURSERY PLANTS, PART I AND II," FLORIDA DEPARTMENT OF AGRICULTURE AND CONSUMER SERVICES OR TO THE STANDARDS AS GIVEN IN THE LATEST "AMERICAN STANDARD FOR NURSERY STOCK", AMERICAN NATIONAL.
- PINE BARK OR PINE STRAW MULCH SHALL BE PROVIDED A MINIMUM OF TWO TO THREE INCHES IN DEPTH AROUND ALL NEWLY PLANTED LANDSCAPE.
- A MULCH RING FOR ALL NEWLY PLANTED TREES SHALL BE PROVIDED AT LEAST FIVE (5) FEET IN DIAMETER AND NOT CLOSER THAN SIX (6) INCHES FROM THE TREE TRUNK.
- IRRIGATION WILL BE PROVIDED WITH AN AUTOMATIC IRRIGATION SYSTEM.
- TREES SHALL HAVE A MINIMUM HEIGHT OF EIGHT (8) TO TEN (10) FEET AND TWO (2) INCHES OF CALIPER.
- SHRUB LINES ARE TO BE PLANTED AT THE REQUIRED MINIMUM HEIGHT, NOT BY CONTAINER SIZE.
- SOIL IN TREE ISLAND SHALL HAVE AT LEAST 12" OF SUITABLE SOIL FOR TREE PLANTINGS, AND BE VOID OF ANY CONSTRUCTION DEBRIS OR UNSUITABLE MATERIALS.
- TREES SHALL NOT BE PLANTED CLOSER THAN 7.5' FROM THE CENTERLINE OF UNDERGROUND UTILITIES.



LANDSCAPE PLAN



ANASTASIA BAPTIST CHURCH
St. Augustine, Florida





↓ 1
ELEVATION


EXISTING
← 4
ELEVATION

← 2
ELEVATION

↑ 3
ELEVATION

EDUCATION BUILDING

1ST FLOOR
17,770 sf



ANASTASIA BAPTIST CHURCH
St. Augustine, Florida





EDUCATION BUILDING

2nd FLOOR  17,770 sf

ANASTASIA BAPTIST CHURCH

St. Augustine, Florida





EDUCATION BUILDING

3rd FLOOR 
12,214 sf



ANASTASIA BAPTIST CHURCH

St. Augustine, Florida



EDUCATION ELEVATIONS




1 EAST ELEVATION - EDUCATION BUILDING



2 SOUTH ELEVATION - EDUCATION BUILDING



ANASTASIA BAPTIST CHURCH
St. Augustine, Florida



EDUCATION ELEVATIONS



3 WEST ELEVATION - EDUCATION BUILDING



4 NORTH ELEVATION - EDUCATION BUILDING



ANASTASIA BAPTIST CHURCH

St. Augustine, Florida



EXTERIOR PAINT COLORS



1. METAL MECHANICAL SCREEN




2. SLOPED ROOF- ASPHALT SHINGLES
-COLOR TO MATCH EXISTING



3. PAINTED STUCCO ON CMU
-TO MATCH EXISTING



4. PREFABRICATED METAL CANOPY



PROPOSED GYMNASIUM BUILDING CONSTRUCTION



ANASTASIA BAPTIST CHURCH
St. Augustine, Florida



EXTERIOR PAINT COLORS



ALPINE WHITE

LIGHT GREY

TUDOR BEIGE

EXISTING BUILDING PAINT COLOR



PROPOSED GYM & EDUCATION BUILDING PAINT COLOR




ANASTASIA BAPTIST CHURCH
St. Augustine, Florida



1 →
ELEVATION

↓ 3
ELEVATION

← 2
ELEVATION



← N
GYMNASIUM
12,230 sf




ANASTASIA BAPTIST CHURCH

St. Augustine, Florida



GYMNASIUM ELEVATIONS



ANASTASIA BAPTIST CHURCH
St. Augustine, Florida



EXTERIOR PAINT COLORS



**1. PRE-FABRICATED METAL PANELS
-TO MATCH ADJACENT STUCCO COLOR**




**2. PAINTED STUCCO ON CMU
-COLORS TO MATCH EXISTING**



**3. SLOPED ROOF- ASPHALT SHINGLES
-COLOR TO MATCH EXISTING**



4. PREFABRICATED METAL CANOPY



PROPOSED GYMNASIUM BUILDING CONSTRUCTION



ANASTASIA BAPTIST CHURCH
St. Augustine, Florida



RENDERINGS



ANASTASIA BAPTIST CHURCH
St. Augustine, Florida



RENDERINGS



ANASTASIA BAPTIST CHURCH
St. Augustine, Florida



RENDERINGS



ANASTASIA BAPTIST CHURCH
St. Augustine, Florida



RENDERINGS



ANASTASIA BAPTIST CHURCH
St. Augustine, Florida



RENDERINGS



ANASTASIA BAPTIST CHURCH
St. Augustine, Florida



RENDERINGS



ANASTASIA BAPTIST CHURCH
St. Augustine, Florida



ATTACHMENT 2
LDC, PART 3.08.00
MID-ANASTASIA OVERLAY
DISTRICT

Part 3.08.00 Mid-Anastasia Overlay District

Sec. 3.08.01 Purpose and Intent

The purpose and intent of this Special District is to achieve specific goals and objectives of the St. Johns County Comprehensive Plan and establish additional requirements which regulate development in a manner that protects natural resources and further supports the provisions of Article IV of this Code, and maintains and enhances the diverse and unique character of the Mid-Anastasia Overlay District.

The objective of these requirements is to protect surrounding residential Uses; cluster complementary Uses; protect scenic views; enhance physical appearance through design and signage controls; protect community character and encourage pedestrian activity. These objectives shall be accomplished through the establishment and implementation of special guidelines, standards and criteria which shall apply to the location, character, compatibility and appearance of proposed cultural, institutional, commercial and multi-family land Uses, and to certain changes or renovations to such existing land Uses. The implementation of this Part shall be assisted by a Design Review Board, which shall be established in accordance with the administrative procedures of this Part. The review of activities which are subject to these additional requirements shall be performed with the goal of determining whether a proposed activity meets the goals, objectives and policies set forth in the Comprehensive Plan and the guidelines, standards and criteria of this Part.

Sec. 3.08.02 Delineation of the Mid-Anastasia Overlay District

- A. The Mid-Anastasia Overlay District, as delineated herein, is a special district in the form of an overlay superimposed upon the various zoning districts. This special district encompasses all that land situated within unincorporated St. Johns County extending from the entrance of Anastasia State Park on the North, extending to Owens Avenue on the South, and the Matanzas River on the West and the Atlantic Ocean on the East.
- B. Delineated roadways within the Mid-Anastasia Overlay District shall include State Road A1A South, State Road 312, Mizell Road, West Pope Road and West 16th Street.

Sec. 3.08.03 Uses and Activities Subject to Mid-Anastasia Overlay District Standards

- A. All standards prescribed in this Part shall apply to all Uses contained within all zoning categories (including PUD's, PSD's, and PRD's) excluding single-family dwellings; Two-Family Dwellings; mobile homes; roadside stands; temporary uses; plant nurseries, barns, corrals, greenhouses and other substantially similar Structures; and boarding stables and riding academies. These requirements shall apply to property proposed for Development as a permitted Use, as well as to additions, exterior remodeling and renovations hereafter undertaken within the Mid-Anastasia Overlay District.
 - 1. Exterior remodeling and renovation shall be defined as any activity changing the exterior of a Structure that requires a County Building Permit, and also the repainting of any Structure to a color other than the existing color, as well as to Construction or alteration of fences or decks.
 - 2. These regulations shall apply to only that portion being added, remodeled, renovated or changed.

3. Landscaping, buffers, signage, parking lots and Structures may be maintained and repaired, Buildings re-painted using the same colors, and roofs repaired and replaced with the same materials and colors, without a review by the Design Review Board (DRB)
4. Any non-conforming Uses or Structures impacted by this Part shall follow Part 10.03.00 of this Code concerning non-conforming regulations.

B. Allowable Uses

The Uses for the property contained within the Mid-Anastasia Overlay District shall be as prescribed in the various zoning districts underlying the Mid-Anastasia Overlay District, except where such Use is not permitted by the St. Johns County Comprehensive Plan.

C. Exemptions

The following activities shall be exempt from review as otherwise required by this Part. In the event of any conflict related to an exempt activity, it shall be the responsibility of the County Administrator to determine that a proposed exempt activity is in compliance with this Part.

1. Repainting of Structures in existing colors.
2. Additions to the rear of a Structure not exceeding two-hundred and fifty (250) square feet which are of similar architectural style as the existing Structure, and consist of like exterior finishes and colors including windows and doors.
3. Replacement of roofing with like roofing materials.
4. Replacement of windows and doors, and existing porches, patio overhangs, porte cocheres or carports which are replaced in a similar style as the existing Structure or main portion of the existing Structure and consist of like exterior finishes and colors.
5. Replacement of landscaping consistent with a previously approved landscape plan or replacement of existing landscaping with like landscaping material.
6. Non-substantive changes, which do not change the character, design or commonly observed appearance of a site or Structure.

Sec. 3.08.04 Development Standards

The following general development standards shall apply within the Mid-Anastasia Overlay District:

- A. Roof design shall be hipped, shed or gable unless otherwise approved by the Design Review Board. Horizontal roofs, which give the appearance of flat roofs, shall not be allowed. Long monotonous facade designs including, but not limited to, those characterized by unrelieved repetition of shape or form or design elements, or by unbroken extension of line shall be avoided. The maximum length of any Building parallel to a roadway shall be 120 feet.

- B. Work areas, storage doors and open bays shall not open toward, face or otherwise be visible from any delineated roadway or any adjacent residential properties. The DRB may consider alternative screening and design concepts to shield work areas, storage doors and open bays from delineated roadway or any adjacent residential properties.
- C. Heating, ventilation and air conditioning equipment, duct work, air compressors, and other fixed operating machinery shall be either screened from view with fencing architecturally compatible with the Building; or vegetation; or located so that such items are not visible from any roadway or adjacent residential properties. Trash receptacles, dumpsters, utility meters, above-ground tanks, satellite dishes (except as provided by Florida law), Antenna, and other such Structures shall be similarly screened or made not visible.
- D. Chain link, barbed wire and similar fencing shall not be allowed in any required Front Yard, and where such fencing can be viewed from any delineated roadway, landscaping or berming shall be provided to prohibit visibility from such roadway or any adjacent residential properties. The fencing and screening provisions of Articles 2.02.04.C and 6.06.04 shall also apply.
- E. Architectural lighting shall be recessed under roof overhangs or generated from a concealed light source, or low level light fixtures. Site lighting shall be of low-intensity, shall be of white light which does not distort colors and shall not spill over into adjoining properties, roadways or in any way interfere with the vision of oncoming motorists. Specifically, lighting shall be downward facing full cut-off, no higher than 20 feet and s all have a maximum illumination level of 0.30 foot-candles at ground level at the lot line.
- F. The maximum vertical clearance of Canopies provided over the pump islands at gas stations, service stations and convenience stores shall not exceed seventeen (17) feet in height from established grade to the underside of the canopy. The maximum height of a canopy shall not exceed twenty-four (24) feet from established grade.

Sec. 3.08.05 Minimum Yard Requirements

- A. Front along State Road AIA South: Twenty (20) feet for a Building up to and including twenty (20) feet in height; ; thirty (30) feet for a Building Above twenty (20) feet in height.
- B. Front along any other delineated roadway: Fifteen (15) feet for a Building up to and including twenty (20) feet in height; twenty (20) feet for a Building above twenty (20) feet in height.
- C. Side: Ten (10) feet.
- D. For Buildings proposed on sites which adjoin an existing residential Use or residentially-zoned Lands, the minimum adjoining a Side or Rear Yard, or both is thirty (30) feet for a Building up to and including twenty (20) feet in height; . Fifty (50) feet for a Building above twenty (20) feet in height.
 - a. Accessory Uses and Structures Accessory uses and structures, Aand parking lots, shall be adequately screened from any Palm Valley Overlay District delineated roadway.
 - b. Accessory Uses and Structures (excluding parking lots), shall not be allowed closer to the Palm Valley Overlay District Delineated Roadway than any Building on the

site.

- F. A distance of eight (8) feet shall separate parking areas and Buildings. This area shall be measured from the exterior wall and shall be used for landscaping and walkways, of which a minimum of three (3) feet shall be used for landscaping.

Sec. 3.08.06 Additional Buffering Requirements

- A. Buffers may be placed within required Yards, and where reasonably possible, shall contain native vegetation existing on the site proposed for Development. In addition to the Buffering and Screening Requirements of Section 6.06.04, the following requirements shall apply in the Mid-Anastasia Overlay District.
 - 1. A minimum twenty (20) foot buffer from the right-of-way of State Road A1A South except Scenic Highway A1A as described in 6.06.02.F.2.b.
 - 2. A minimum fifteen (15) foot buffer from the right-of-way of any other delineated roadway.
- B. The above buffers shall be landscaped in accordance with Section 6.06.04, paragraphs a. and c. of Screening Standards "C", which state:
 - 1. A row of evergreen Canopy Trees which are not less than ten (10) feet high at the time of planting, a minimum of two (2) inch caliper, and are spaced not more than twenty (20) feet apart. The Trees are to be planted within ten (10) feet of the property line; and
 - 2. Lawn, low growing evergreen plants, evergreen ground cover, or mulch covering the balance of the buffer.
- C. The width of a required Buffer shall be measured beginning at the property line. Continuation of landscaping into the right-of-way, where feasible and not otherwise prohibited by these regulations is encouraged. Required buffers shall be included in all plans submitted for review.
- D. Sidewalks and pedestrian seating may be placed in required buffers.
- E. The Design Review Board may request the use of certain vegetation and plant species where an established or preferred species exists on a site or within adjacent development.

Sec. 3.08.07 Additional Signage Requirements

All multi-family and commercial Signs, including new Signs and replacement of existing Signs, shall be governed as set forth in Article VII of this Code, and the following additional requirements shall apply.

- A. General provisions applying to multi-family and commercial Signs in the Mid-Anastasia Overlay District:
 - 1. All Ground Signs shall be wide-based monument style. Pylon Signs are only permitted when monument style signs cannot be adequately located due to site

constraints as determined by the DRB.

2. The overall height of a Sign Structure shall be twelve (12) feet including any foundation supporting the Sign. A foundation used to support a Sign shall not exceed four (4) feet in height. The use of dirt, sand or other material to elevate the height of a Sign on a mound is prohibited.
 3. The colors and materials of Signs shall be similar to and compatible with the architectural style and colors and materials of the related commercial or multi-family Building. Any icons that is not similar to and compatible with the architectural styles, colors, and materials of the related building shall be restricted to a maximum fifteen percent (15%) of the advertising display area, unless additional area is approved by the DRB.
 4. Signs should be oriented to pedestrians and scaled appropriately.
 5. Signs must be professionally designed, lettered and constructed.
 6. Signs may be double faced.
 7. Wall Signs shall be mounted directly upon wall surfaces, and shall not be mounted upon raceways or other protrusions from the wall surface.
 8. All ground or pylon Signs shall include the street number in a size and manner that is clear and visible. Street numbers should also be visible on the front of buildings.
 9. In construing the provisions of this Section, messages not exceeding six (6) inches in height erected within or upon doors and windows shall not be counted in computing the number of Signs.
 10. Any lighting shall be white in color for all signs, unless different lighting is required by the County for purposes of protecting turtles. External lighting must conceal and shield the light.
 11. Molded vinyl or plastic internally illuminated wall Signs shall not be allowed.
 12. For Signs that contain federally registered trademarks or service marks, documentation of such registration shall be provided with the application for review.
 13. Where feasible, as determined by the approval authority, all Ground Signs shall use shrubs that are twenty-four (24) inches at the time of planting around the base of the sign. These must be planted within 30 days of the sign installation.
- B. Ground or Pylon Signs: Number and size of Signs permitted for the street frontage
1. **For Sites five (5) acres or less:** One (1) on-site Sign, not to exceed thirty-two (32) square feet for each Sign Face, may be located on each arterial or collector street frontage.
 2. **For Sites more than five (5) acres:** One (1) on-site Sign, not to exceed sixty (60) square feet for each Sign Face, may be located on each arterial or collector street

frontage.

3. New Ground Signs and alterations to existing Ground Signs requiring a DRB review shall be externally illuminated with downward facing fixtures and hours of illumination to cease no later than 30 minutes after business closing, unless additional time is approved by the DRB.

C. Additional Directional Signs Allowed

In addition to the above Signs, two directional Ground Signs limited to two (2) square feet per Sign are allowed. The maximum allowable height shall be three (3) feet.

D. Commercial Wall, Hanging and Awning Signs: **Single-Story Buildings**

1. In addition to the above Signs, a commercial use is allowed one wall Sign not to exceed twenty-four (24) square feet and may be allowed on each street side of the Building.
2. Where a single-story Building is divided into units for several businesses, with separate entrances, one wall Sign as specified above is authorized for each business entrance, not to exceed twenty-four (24) square feet in advertising display area. In addition, each business entrance may have one double-faced hanging Sign under covered walkways with maximum dimensions of two (2) feet vertical by four (4) feet horizontal.
3. One awning Sign or one window identification Sign may be substituted for a wall Sign, with sign display area not to exceed twenty-four (24) square feet in area.

E. Commercial Wall, Hanging and Awning Signs: **Multi-Story Buildings**

1. Where a multi-Story Building is divided into units or floors for several businesses, one wall Sign, not exceeding twenty-four (24) square feet of area, may be allowed on each street side of the Building.
2. In addition to the above Wall Sign, where a multi-Story Building is divided into units or floors for several businesses, one awning Sign, not exceeding twenty-four (24) square feet of display area, may be allowed over each first story entrance, provided that any such awning sign is an integral and unified part of the architectural design of the entire building.
3. One double-faced hanging Sign under covered walkways with maximum dimensions of two (2) feet vertical by four (4) feet horizontal is allowed for each business entrance.

F. Multiple Tenant Directory Signs

For office and professional Buildings with multiple tenants, one directory Sign containing only the suite number, the names of individuals, organizations or businesses occupying the Building not exceeding fifteen (15) square feet of face area is allowed. Such signs may be wall signs or ground signs. Such signs are permitted in addition to any other allowed signs.

G. Prohibited Signs

In addition to those Signs prohibited within Section 7.08.01, the following Signs are prohibited in the Mid-Anastasia Overlay District.

1. Flashing or animated Signs with any moving parts.
2. Signs painted on, or displayed from the roof of any Building or Structure.
3. Statues, flags, banners, pennants, and inflatables used for advertising purposes, except as may be allowed by Article VII and Section 3.08.07.I of this Part.
4. Exterior Signs containing exposed neon, except those specifically approved by the Design Review Board and found consistent with the Purpose and Intent of this Part.
5. Interior neon window Signs, which exceed more than thirty percent (30%) of window area. In no case shall an interior neon sign exceed twelve (12) square feet.

H. The following provisions apply to temporary signage:

1. Banner signs shall be allowed between the timeframe of overlay application submittal and up to a period of sixty (60) days after permanent sign approval by the DRB. This shall consist of no more than three (3) signs at a maximum advertising display area of twenty-four (24) square feet each.
2. Banner signs shall be allowed in accordance with Section 7.05.00 and 7.07.01.A for a period of sixty (60) days per calendar year, not to exceed one (1) time in one (1) month and not to exceed ten (10) days per each event. This shall consist of no more than three (3) signs at a maximum advertising display area of sixty (60) square feet each.

I. Administrative Approval of Specific Signage

1. Any ground sign reface thirty-two (32) square feet or portion thereof in size provided the colors closely match any colors associated with the building and text type/sizes are similar to other DRB approved signage located on the ground sign face.
2. Any Wall, Awning or Window Sign reface twenty-four (24) square feet or any Hanging Sign up to eight (8) square feet or portion thereof in size provided the colors closely match any colors associated with the Building and text type and sizes are similar to other DRB approved signage located on existing Wall Signs on the same Building.
3. Any Directional Sign that is two (2) square feet or less in size.
4. Any wall, awning, ground, hanging and/or window identification signage within a Unified Sign Plan that is approved by the DRB.

J. Unified Signage Plan (USP)

The USP is an elective master plan for all Project (wall, ground, awning, and window) identification signs located for multi-family and commercial properties. The purpose of the USP is to develop a cohesive sign strategy/design that meets code, expresses the desire of the DRB, and allows an expedited approach to review signage. The USP shall follow the below requirements:

1. All signage must adhere to the overlay district code.
2. The USP shall provide information relating, but not limited, to the size of the advertising display area (minimum and maximum), type of sign (i.e. box or individual letter), mounting procedures, lighting, colors, font, materials, icons, and any other relevant information required by the County.
3. The DRB must consider the USP prior to approve of the USP and may require any conditions it finds necessary to meet the purpose and intent of the overlay code.

L. Signs Exempt from this Part

Real Estate for Sale or Lease, Contractor Identification Signs, trespass and alarm warning Signs, which are in compliance with the requirements of this Section are Exempt from this Part. However, if in the determination of the County Administrator, any Signs may be in conflict with the Purpose and Intent of the Mid-Anastasia Overlay District, a review by the Design Review Board may be required and appropriate modifications ordered.

Sec. 3.08.08 Design Review Guidelines

The pleasing and compatible relationship of architecture and design elements within the Mid-Anastasia Overlay District is of important public concern. The design of Structures and their materials and colors must be visually harmonious with the overall appearance, history and cultural heritage of the Mid-Anastasia Overlay District. Development must also be compatible with the natural landforms, existing coastal vegetation, dune systems and native beach and estuarine environments. Compatibility with existing adjacent Structures and approved development plans must also be considered. The intent of these standards is not to restrain diversity or innovative architecture, but to reduce incompatible and adverse impacts, and to insure an aesthetically pleasing environment. To accomplish this, the following guidelines shall apply to new Buildings, certain exterior renovations, and related site improvements.

- A. Proposed Development shall be located and configured in a visually complementary manner with the existing terrain and vegetation of the Parcel and surrounding Parcels. Structures shall obstruct as little as reasonably practical scenic views from the main road or from existing Structures and the natural environment. Structures shall not dominate any general Development or adjacent Building that is substantially in compliance with this Code. This may be accomplished by the use of architectural features and/or siting of proposed Structures to reduce the appearance of excessive and inappropriate height or mass of proposed Structures.
- B. New Buildings shall be designed to contribute to the image of the Mid-Anastasia Overlay District as a beach community with a pedestrian-oriented, non-urban scale and character.
- C. Buildings that are reflective of Florida's wood-frame vernacular architectural styles such as "Florida Cracker", shingle and low-country, Spanish Eclectic, Craftsman and Bungalow

styles shall be considered appropriate.

- D. To encourage pedestrian activity, buildings should where possible incorporate the following design patterns and details:
 - 1. A Building's main entrance should face the main roadway. Buildings located at street corners should have entrances at the corner.
 - 2. Blank walls facing the main roadway should be avoided. The use of entrance ways and display windows should be used to create business and store fronts that are inviting to the pedestrian.
- E. Outdoor pedestrian seating areas are encouraged, and similarly, outdoor cafe-type seating is encouraged.

Sec. 3.08.09 Design Elements and Materials

The following specific design criteria shall apply to Development regulated by the Mid-Anastasia Overlay District:

- A. Roofs shall consist of wood or asphalt composition shingles, barrel tile, clay tile or similar non-reflective material having a natural texture and appearance. Metal roofs shall be allowed where they are characteristic of a recognized architectural style.
- B. Exterior walls on all sides shall be stucco, tabby, shingle, wood siding, exterior insulation-and-finish systems (EIFS), brick or other materials with similar texture and appearance. The DRB may consider other materials which are similar to the finishes listed above and provide for a cohesive building concept.
- C. Exterior colors of paints and stains of new Construction or Development shall be subdued and nature-blending with no more than three (3) colors per Building, excluding roof color. The DRB may allow up to two (2) additional colors for building accents (e.g. trim, awnings, columns, and shutters). Such hues of green, brown, blue, grey, tan and beige shall be considered appropriate. Public art such as murals will not be applicable to the color standards in this paragraph. The design of the mural will not exceed a maximum of fifteen percent (15%) of the façade in which it is located unless additional area is approved by the DRB.
- D. Roof and exterior wall surfaces, with the exception of glass doors and windows shall be non-reflective. Any glass coating shall not reflect outward and shall be limited in color to gray or green.
- E. Administrative Approval of Design Elements, Materials, and Exterior Finishes
 - 1. The Design Review Board, shall, with assistance of the County, develop architectural design guidelines in accordance with Section 3.08.01 of this Part. Such guidelines shall be adopted by the Board of County Commissioners and shall, at a minimum, include color palettes for exterior materials and finishes.
 - 2. Upon the adoption of color palettes for exterior materials and finishes, exterior painting of existing Structures and Buildings with a selection from the preferred color

palette may be approved by the County Administrator. However, if in the determination of the County Administrator, any proposed exterior painting appears to be in conflict with the Purpose and Intent of the Mid Anastasia Overlay District or with the preferred color palette, a review by the Design Review Board may be required.

Sec. 3.08.10 Administrative Requirements

The following requirements shall apply to all projects and activities that are subject to the Mid-Anastasia Overlay District. For those projects involving Signs less than fifteen (15) square feet in size, Ground and Wall Sign re-faces, re-painting, or other activities not requiring a County building permit, a minor review application shall be allowed. Additionally, a minor review shall be allowed for those other projects, which are determined by the County Administrator to be minor in nature. For all other projects, a regular review application shall be required.

A. Functions and Establishment of the Design Review Board

The St. Johns County Board of County Commissioners shall direct the following functions to determine compliance with the Mid-Anastasia Overlay District:

1. The St. Johns County Board of County Commissioners shall establish by appointment a Design Review Board. Except as otherwise provided in this Code, it shall be the role of the Design Review Board to determine compliance with this Part.
2. The Design Review Board shall consist of five (5) members and two (2) alternates. Membership qualifications and the initial membership term shall be set by resolution of the Board of County Commissioners. The initial terms shall be staggered in 1, 2, 3, and 4 year terms. Except for the initial term, members shall be appointed to a four (4) year term, with an additional four (4) year term as approved by the Board of County Commissioners. Members shall serve at the pleasure of the Board of County Commissioners.
3. The Board of County Commissioners shall adopt by Resolution bylaws, operating procedures, and membership requirements of the DRB which shall be in accordance with all applicable St. Johns regulations Codes and State and Federal laws. The DRB may recommend changes to its bylaws, operating procedures, and membership criteria, to be approved by the Board of County Commissioners.
4. The Design Review Board shall meet as needed in order to fulfill its functions in a timely manner. Reasonable public notice shall be provided for all meetings of the Design Review Board, and all meetings shall be open to the public. The Design Review Board shall appoint a member or support staff to keep minutes of its proceedings and other official actions. A majority vote of a present quorum shall be required in order to take final action on an application.
5. Any previous citizen appointed to the DRB shall have the opportunity to reapply and have the same term limits as prescribe in subsection A.2, provided they have not been excluded by the Board of County Commissioners because of longevity on the DRB. If longevity is an issue, the citizen must wait a period of two (2) years from the date of their original expiration before reapplying to the DRB.

B. Application and Permitting Requirements

1. The County Administrator shall develop application forms and review procedures to assist the Design Review Board in determining compliance with the Mid-Anastasia Overlay District requirements. The Design Review Board shall meet as required to review applications and take action in a timely manner on all applications submitted for review.
2. Following any final action, the Design Review Board or its authorized support staff shall provide a written order to the Applicant stating that the request complies, complies with conditions, or does not comply, with the Mid-Anastasia Overlay District requirements. Any determination by the Design Review Board shall be supported by appropriate findings of fact.
3. The Applicant shall provide a copy of the final order of approval prior to obtaining construction permits as required for the proposed project or activity.
4. In general, all applications that are subject to the County's established development review process shall proceed through a first submittal development review prior to being scheduled for the Design Review Board. Any DRC comments that have not been addressed at the time of Design Review Board meeting shall be noted by the Applicant. If appropriate, the Design Review Board may attach conditions to its determinations related to outstanding development review comments. The Design Review Board shall not request modifications that are not in compliance with other land development regulations.

C. Vested Rights Determinations

1. As an alternative to a determination that a Project or activity complies with this Part, the Applicant may demonstrate that vested rights to proceed with the proposed Project or activity have been legally established, and/or demonstrate that the County is equitably estopped from applying Part 3.08.00 of this Code. Vested rights determinations shall be made in accordance with Part 10.02.00 of this Code. The legal requisites for such determinations and burdens of proof shall be those provided by applicable Federal and State Law. Applicants shall have the burden of demonstrating vested rights or equitable estoppel.
2. A Planned Unit Development (PUD) may be expanded, without a vested rights or estoppel determination, if the proposed addition(s) adjoins the existing PUD. The more restrictive standards and criteria of the existing PUD or the Mid-Anastasia Overlay District shall apply to the expansion.

D. Variances and Appeals

An Applicant may apply and be granted or denied a Variance from one or more standards of this Part. Variances or modifications to these requirements shall be governed as follows:

1. Any Variance or modification within existing PSD/PUDs to these requirements may be granted only by the Board of County Commissioners. Notwithstanding any other provision in the Land Development Code, such requests shall be considered by the Board of County Commissioners as a Non-Zoning variance pursuant to the requirements of Section 10.04.03 of this Code in lieu of the procedures set forth in

Section 5.03.05. Requests to change specific provisions not pertaining to the District requirements within PUDs and PSDs shall be processed pursuant to Section 5.03.05.

2. Any affected or aggrieved person may Appeal a written determination of the Design Review Board to the Board of County Commissioners, in accordance with Section 9.07.04, by filing such Appeal in writing to the County administrator within thirty (30) days of any such written determination.

E. Management of Applications among Multiple Boards

1. When a board or agency has made a decision or finding on an application, and the application or companion application will later appear before the Board of County Commissioners, its approval or approval with conditions shall constitute a recommendation to the Board of County Commissioners. The Board of County Commissioners may choose to accept the decision or finding of the board or agency, make a binding decision or finding of its own, or send the application back to the board or agency for a decision consistent with the Board of County Commissioners findings or suggestions.
2. This section does not impose any additional review standards on applications or board or agency decisions as set forth in this Code.

F. **Administrative Approval**

1. Delegation of Signing Authority. In the event that the Design Review Board has determined compliance with this Part, the DRB may authorize its support staff to sign and render and Order approved by the DRB in lieu of the Chair or Vice-Chair.
2. Failure to Hold a Quorum. In the event that the Design Review Board is unable to gather a quorum to render a decision on an application scheduled for a hearing before the DRB and is unable to gather another quorum within ten (10) days of the scheduled hearing, the County Administrator shall determine compliance with the provisions of the Mid-Anastasia Overlay District.
3. Failure to Establish a Design Review Board. Failure in the event that the St. Johns County Board of County Commissioners are unable to establish a Design Review Board as defined by this Part, it shall be the responsibility of the County Administrator to determine compliance with the provisions of this Part. Failure to establish shall mean that at any time there are less than three (3) regular members appointed to the DRB.

ATTACHMENT 3
DRAFT FINAL ORDERS
APPROVAL / DENIAL



ORDER OF THE ST. JOHNS COUNTY, FLORIDA
DESIGN REVIEW BOARD
OF THE MID-ANASTASIA OVERLAY DISTRICT

Brian Couch, KBJ- L&B Architects
50 N. Laura Street, Suite 4200
Jacksonville, FL 32202

FILE NUMBER: MADRB 2021-06 Anastasia Baptist Church
PARCEL: 161870-0000
DATE OF HEARING: March 10, 2022

ORDER GRANTING APPROVAL

The above referenced application, **MADRB 2021-06 Anastasia Baptist Church**, a request for design approval for demolition of the existing Educational/Administration Buildings and detached office building, and approval for construction of two new buildings to include an Education/Administration Building and a Gymnasium located at **1650 A1A South** was considered by the Mid-Anastasia Design Review Board (MADRB) in a public hearing.

FINDINGS OF FACT

Having considered the application, supporting documents, statements made by the Applicant and Staff, and all evidence presented during the public hearing, the Board made the following Findings of Fact:

- 1. The request is consistent with Section 3.08.00 of the St. Johns County Land Development Code and will meet all other Code requirements.**

NOW THEREFORE, based on said Findings of Fact, the Board hereby approves this application as submitted subject to the following conditions.

- 1. Any changes to the original application as submitted will require additional review by the Mid-Anastasia Design Review Board.**

This decision may be appealed to the St. Johns County Board of County Commissioners within thirty (30) days of the signing of this Order, pursuant to Section 9.07.04 of the Land Development Code. Deed Restrictions, if any, are not affected by the actions of the Board or this Order.

All applicable state or federal permits must be obtained before commencement of the development. Issuance of a development permit or development order by a county does not in any way create any rights on the part of the applicant to obtain a permit from a state or federal agency and does not create any liability on the part of the county for issuance of the permit if the applicant fails to obtain requisite approvals or fulfill the obligations imposed by a state or federal agency or undertakes actions that result in a violation of state or federal law.

DATED THIS _____ DAY OF _____, 2022.

DRB FOR THE MID-ANASTASIA OVERLAY DISTRICT WITHIN ST. JOHNS COUNTY, FLORIDA:

BY: _____
Bob Boese, Chair

The undersigned Clerk of the Board certifies that the above Order is a true and correct copy of the Order adopted by said Board as the same appears in the record of the Board Minutes.

BY: _____
Clerk: Saleena Randolph, Planner
Attachment: Stamped approved drawings



ORDER OF THE ST. JOHNS COUNTY, FLORIDA
DESIGN REVIEW BOARD
OF THE MID-ANASTASIA OVERLAY DISTRICT

Brian Couch, KBJ- L&B Architects
50 N. Laura Street, Suite 4200
Jacksonville, FL 32202

FILE NUMBER: MADRB 2021-06 Anastasia Baptist Church
PARCEL: 161870-0000
DATE OF HEARING: March 10, 2022

DENIAL ORDER

The above referenced application, **MADRB 2021-06 Anastasia Baptist Church**, a request for design approval for demolition of the existing Educational/Administration Buildings and detached office building, and approval for construction of two new buildings to include an Education/Administration Building and a Gymnasium located at **1650 A1A South** was considered by the Mid-Anastasia Design Review Board (MADRB) in a public hearing.

FINDINGS OF FACT

Having considered the application, supporting documents, statements made by the Applicant and Staff, and all evidence presented during the public hearing, the Board made the following Findings of Fact:

- 1. The request is not consistent with Section 3.08.00 of the St. Johns County Land Development Code.**

NOW THEREFORE, based on said Findings of Fact, the Board hereby denies this application as submitted.

This decision may be appealed to the St. Johns County Board of County Commissioners within thirty (30) days of the signing of this Order, pursuant to Section 9.07.04 of the Land Development Code. Deed Restrictions, if any, are not affected by the actions of the Board or this Order.

All applicable state or federal permits must be obtained before commencement of the development. Issuance of a development permit or development order by a county does not in any way create any rights on the part of the applicant to obtain a permit from a state or federal agency and does not create any liability on the part of the county for issuance of the permit if the applicant fails to obtain requisite approvals or fulfill the obligations imposed by a state or federal agency or undertakes actions that result in a violation of state or federal law.

DATED THIS _____ DAY OF _____, 2022.

DRB FOR THE MID-ANASTASIA OVERLAY DISTRICT WITHIN ST. JOHNS COUNTY, FLORIDA:

BY: _____
Bob Boese, Chair

The undersigned Clerk of the Board certifies that the above Order is a true and correct copy of the Order adopted by said Board as the same appears in the record of the Board Minutes.

BY: _____
Clerk: Saleena Randolph, Planner